BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18650/CALL-2

APPROVED SCHEDULE - B

EE/B BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Construction of Drains in Military Dairy Farm in Sanjeevininagar Ward No .7, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R SATHEESH		
				In Figures		In Words
1	600	KSRRB 200-8, Clearing and grubbing road land including uprooting rank vegetation, grass,brush, shrubs,saplings and trees of girth upto 300mm,by manual means,in area of light jungle,removal od stumps,disposal of unservicable materials,stacking of servicable materials within a lead of 100metres from road boundary ,labour charges complete as per Specification	Sqm	6.0	3600.00	Rupees Six Only
2	1500	KSRRB 200-8, Clearing and grubbing road land including uprooting rank vegetation,grass,brush,shrubs,saplings and trees of girth upto 300mm,by manual means,in area of Thorney jungle,removal od stumps,disposal of unservicable materials,stacking of servicable materials within a lead of 100metres from road boundary ,labour charges complete as per Specification	Sqm	10.0	15000.00	Rupees Ten Only
3	1162.5	KSRRB 300-11. Excavation for road way in all type soil by mechanical means including cutting and pushing the earth to site of embankment including trimming bottom and side slopes in accordance with requirements of lines,grades and cross sections complete as per specifications.	Cum	80.0	93000.00	Rupees Eighty Only
4	132	KSRRB 2.2.6.Excavation 1.5m and above in width in hard rock by chiselling and / or wedging,where blasting is prohibited for foundation of buildings,water supply,sanitary lines and electrical conduits either in pits or in trenches 1.5 m in depth stacking the excavated stuff clear from the edge of excavation with lead upto 50m including cost of labour complete as per specifications.	Cum	1350.0	178200.00	Rupees One Thousand Three Hundred Fifty Only
5	487.5	KSRB5 M300-53, Construction of embankment with approved material Gravel/Murrumwith all lifts and leads,transporting to site,spreading,grading to required slope and compacting to meet requirements Table 300-2 complete as specification (which includes cost of gravel/murrum,watering charges & compaction by vibratory	Cum	315.0	153562.50	Rupees Three Hundred Fifteen Only
6	105	Providing and laying cement concrete pipe NP3 for culvertsincluding pointing ends,and fixing collars with cement Mortar 1:2 including cost af all materials labour,curing complete as per specifications	Rmt	4140.0	434700.00	Rupees Four Thousand One Hundred Forty Only
7	24	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6)including fixing curing etc complete 10.00cm Thick	Sqm	900.0	21600.00	Rupees Nine Hundred Only
8	1294.5	KSRRB M100-1 Loading and unloading os stone boulder/stone aggregates/sand/kanker/moorum.KSRRB M100-1 : Pacing tipper at loading point, loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip completeas per specifications.	Cum	80.0	103560.00	Rupees Eighty Only
9	1294.5	KSRRB M100-4.3.Haulage of materials by tipper excluding cost of loading,unloading and stacking completeas per specifications. Morth Chapter 1 case - III : Katcha Track and track in river bed/Nallah bed and choe bed for a distance of	Cum	5.5	7119.75	Rupees Five and Fifty Paise Only
10	78	Providing and constructing pitching / revetment of 30 cm thick on slopes using granite/Basalt/trap/stones of surface rea not less than 0.04 sqm and wedged with spalls including cost of all materials labour etc complete as per specifications. Specification	Cum	420.0	32760.00	Rupees Four Hundred Twenty Only
		Total			1043102.25	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

01/03